## ANJANAPUR DIVISION.

*Abstract Notification dated 23rd February* 1940.

The attention of the public is drawn to the Notification calling for tenders for constructing a Circle 100 feet diameter at entrance to waste weir of Anjanapur Reservoir, Shikaripur Taluk, published on pages 441-442, Part VI of the *Mysore Gazette*, dated 29th February 1940.

2. The tenders will be received by the Executive Engineer upto 12 NOON on 1st April 1940.

3. The earnest money required for the work is Rs. 140 which should be credited to the Treasury to "17. (*a*) P. W. Deposits" and the relative chellan enclosed.

M. V. KRISHNASWAMY IYENGAR,
*Executive Engineer.*

## KADUR DIVISION.

*Abstract Notification dated 18th February* 1940.

The attention of the public is invited to the Notification, published on pages 380-383, Part VI of the *Mysore Gazette*, dated 22nd February 1940, calling for tenders for the work of "constructing a row of shops in the compound of Sri Sringeri Mutt at Tarikere, Tarikere Taluk."

The last date of receipt of tender in this office is 9th March 1940.

---

*Notification dated 25th February* 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, up to 12 NOON on 16th March 1940, for constructing Dispensary Buildings at Bukkambudi, Tarikere Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kadur Division, Chikmagalur, on payment of annas four per each form should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, in a sealed cover and superscribed as "Tender for constructing Dispensary Buildings at Bukkambudi, Tarikere Taluk." The name of the tenderer should also be superscribed on the top left cover.

3. Each tender must be accompanied by a deposit of Rs. 380 (rupees three hundred and eighty only) in cash or Government Promissory Notes or My or Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date at the time of opening. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chikmagalur, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the Contractor are only tentative and are liable to alterations, omissions, deductions or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1940, failing which, the Executive Engineer may, at his discretion, levy a penalty of Rs. 100 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. Chamundi brand cement must be used for the work.

23. The contractor should arrange for the payment of royalty and tolls.

*Note.*—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills, and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

*Note*—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for constructing Dispensary Buildings at Bukkambudy, Tarikere Taluk.

| No. | Particulars | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | *I. Dispensary Building with Emergency Ward.* | | Rs. a. p. | | Rs. |
| 1 | Earthwork excavation for foundation in hard soil and filling in basement, watering, tamping, etc., complete .. .. .. .. | C.yd. | 0 4 0 | 55 | |

| No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 2 | Stone jelly concrete in lime mortar 1 : 2 for foundation .. .. .. .. | C.ft. | 0 4 0 | 319 | |
| 3 | Size stone in mud for foundation and basement with through bond stones at intervals of 6′ apart in every course and quoin dressing to basement .. .. .. .. | ,, | 0 4 0 | 1,135 | |
| 4 | Supplying and fixing burnt stone slabs in lime mortar of 6″ thick, one line dressed for exposed faces, including joints for basement .. | S.ft. | 0 10 0 | 348 | |
| 5 | Burnt brick in lime mortar for superstructure .. | C.ft. | 0 4 0 | 1,724 | |
| 6 | Supplying and fixing T. W. doors of 3″×4″ frames, with $1\frac{1}{4}$″ thick $\frac{1}{3}$ panelled and $\frac{2}{3}$ glazed shutters with iron hinges, bolts, nuts, tower bolts, etc., complete as per approved design .. .. .. .. .. | S.ft. | 1 12 0 | 28 | |
| 7 | Supplying and fixing T. W. doors with frame of 3″×4″ with ledged shutters of $1\frac{1}{4}$″ thick with bolts, nuts, screws, etc., complete .. | ,, | 1 8 0 | 149·50 | |
| 8 | Supplying and fixing T. W. windows with frames of size 3″×4″ and $1\frac{1}{4}$″ thick shutters $\frac{1}{2}$ panelled and $\frac{1}{2}$ glazed cut into 4 halves with $\frac{3}{4}$″ round iron bars, bolts, nuts, hinges, screws, etc., complete .. .. .. .. | ,, | 2 0 0 | 64·5 | |
| 9 | Supplying and fixing T. W. ventilators with iron fittings, etc., complete including glazed shutters and $\frac{3}{4}$″ round iron bars .. | ,, | 1 8 0 | 24 | |
| 10 | Supplying and fixing burnt stone slabs of $4\frac{1}{2}$″ thick in lime mortar .. .. .. | ,, | 0 8 0 | 87 | |
| 11 | Constructing pillars of burnt brick in cement composite mortar (1 : 6) 9″×9″ sq. with base and capital as per approved design 8′ depth with 4″ thick bond slabs at vertical intervals of $2\frac{1}{2}$′ including chunam plastering, white washing, etc., complete .. .. | No. | 10 0 0 | 6 | |
| 12 | Casting and curing R.C.C. beams (1 : 2 : 4) with reinforcements as per design of 6″×8″ section over verandah pillars exposed faces cement plastered and finished smooth .. .. | C.ft. | 2 4 0 | 15 | |
| 13 | Teakwood wrought and put up complete including wood oiling 2 coats .. .. .. | ,, | 4 8 0 | 96·22 | |
| 14 | Roofing with 1st class Mangalore tiles on teak reepers 2″×1″ including fixing, etc., complete. | Sqr. | 25 0 0 | 9·07 | |
| 15 | Roofing with Madras Terrace on teak wood joists, with 3″ of brick on edge $4\frac{1}{2}$″ of kappi concrete and 2 coats of flat tiles finished to proper slope with nice asphaltic plastering on top. | ,, | 40 0 0 | 1·99 | |
| 16 | Chunam mortar plastering .. .. .. | ,, | 4 0 0 | 32·32 | |
| 17 | Whitewashing 2 coats after scraping .. .. | ,, | 0 4 0 | 32·32 | |
| 18 | Cement pointing to basement ( 1 : 3) .. | ,, | 3 8 0 | 1·83 | |
| 19 | Flooring with $1\frac{1}{2}$″ cement concrete (1 : 2 : 4) on a bed of 3″ lime jelly concrete (1 : 2) with $\frac{1}{2}$″ cement plastering (1 : 3) top finished with coloured cement with cut lines, etc., complete. | ,, | 20 0 0 | 6·19 | |
| 20 | Government Lac Factory green painting 2 coats | ,, | 4 0 0 | 5·32 | |
| 21 | Providing mortar band cornice as per design $4\frac{1}{2}$″ deep .. .. .. .. .. | R.ft. | 0 6 0 | 39 | |
| 22 | Ridge tiles set in lime mortar and cement pointed | ,, | 0 8 0 | 81·50 | |
| 23 | Supplying and fixing teakwood eaveboard $\frac{3}{4}$″ thick and 9″ deep including painting, etc., complete .. .. .. .. | ,, | 0 8 0 | 66 | |

| No. | Particulars | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 24 | Constructing 9″ cornice alround main building for lean-to roof as per approved design .. | R.ft. | 0 12 0 | 70¼ | |
| 25 | Supplying and fixing teakwood finials as per approved design .. .. .. | No. | 2 0 0 | 2 | |
| 26 | Supplying and fixing teakwood pendants as per approved design .. .. .. | ,, | 1 0 0 | 4 | |
| 27 | Constructing sink and oven in bath room as per approved type .. .. .. .. | L. S. | .. | | |
| 28 | Carving figure and painting with Japan (Dispensary) in front verandah as per approved design | ,, | .. | .. | |
| 29 | Supplying and fixing T. W. counter board in the compounding room as per approved design with pegs, etc., complete .. .. .. | S.ft. | 0 8 0 | 21 | |
| 30 | Providing down water outlet pipes of plain zinc sheet (4″×3″) .. .. .. .. | No. | 2 0 0 | 5 | |
| 31 | Providing and fixing T. W. screen of approved design with 3″×3″ frames including ornamental base and capital with iron fittings, etc., complete .. .. .. .. | S.ft. | 0 8 0 | 39 | |
| 32 | Providing and fixing stone parapet wall with stone balusters with base and capital as per approved design with plinter and coping slabs and three line dressing, etc. .. .. | R.ft. | 2 8 0 | 28 | |
| | *Constructing Latrine.* | | | | |
| 1 | Earthwork excavation and filling in sides .. | C.yd. | 0 3 0 | 1 | |
| 2 | Burnt brick in cement combination mortar (1 : 6) | C.ft. | 0 6 0 | 141 | |
| 3 | Cement plastering ½″ thick (1 : 3) .. .. .. | Sqr. | 8 0 0 | 1·17 | |
| 4 | Chunam plastering .. .. .. .. | ,, | 4 0 0 | 3·77 | |
| 5 | Flooring with 1½″ cement concrete on a bed of 3″ lime jelly concrete top finished with ½″ cement plaster and coloured cement, etc., complete .. .. .. .. .. | ,, | 20 0 0 | 0·64 | |
| 6 | Providing drains inside by grooving and finishing, etc., complete (1½″ deep) .. .. | R.ft. | 0 2 0 | 16 | |
| 7 | Providing G. I. pipe outlets .. .. | No. | 1 0 0 | 2 | |
| 8 | Providing drains 6″ deep and 6″ wide in surki combination mortar concrete and finished with cement plastering nice .. .. .. | R.ft. | 0 8 0 | 60 | |
| 9 | Providing slump pits of approved type .. | L. S. | .. | | |
| | *II. Maternity Ward.* | | | | |
| 1 | Earthwork excavation in hard soil including filling in basement watering, tamping, etc., complete .. .. .. .. | C.yd. | 0 4 0 | 30 | |
| 2 | Lime jelly concrete (1 : 2) .. .. .. | C.ft. | 0 4 0 | 164 | |
| 3 | Size stone in mud for foundation with through bond stones at intervals of 6′ apart in every course including quoin dressing to basement. | ,, | 0 4 0 | 718 | |
| 4 | Burnt brick in lime mortar for superstructure .. | ,, | 0 4 0 | 1,249 | |
| 5 | Supplying and fixing teakwood doors of 3″×4″ frames with 1¼″ thick, ⅓ panelled and ⅔ glazed shutters, with iron hinges, bolts, nuts, and tower bolts, etc., complete as per design. | S.ft. | 1 12 0 | 39 | |
| 6 | Supplying and fixing T. W. doors with frames of 3″×4″, with ledged shutters 1¼″ thick, with bolts, nuts, screws, etc., complete .. | S.ft. | 1 8 0 | 73·12 | |

| No. | Particulars | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 7 | Supplying and fixing T. W. windows of frames 3″×4″ with 1¼″ thick shutters ½ panelled and ½ glazed cut into 4 halves with ¾″ round iron bars, bolts, nuts, hinges, screws, etc., complete | S.ft. | 2 0 0 | 24 | |
| 8 | Supplying and fixing T. W. ventilators of 3″×4″ frames and of 1¼″ thick glazed shutters with ¾″ round iron bars, bolts, nuts, hinges, screws, etc., complete | ,, | 1 8 0 | 12·37 | |
| 9 | Supplying and fixing burnt stone slabs of 4½″ thick in lime mortar (and one line dressing to exposed faces) | ,, | 0 8 0 | 69 | |
| 9a | Supplying and fixing burnt stone slabs of 6″ thick, in lime mortar and one line dressing to exposed faces | ,, | 0 10 0 | 196 | |
| 10 | Supplying and fixing T. W. pillars of 6″×6″ sqr. with stone base and wooden capital as per approved design | No. | 12 0 0 | 2 | |
| 11 | Teakwood wrought and put up including 2 coats of wood oiling | C.ft. | 4 8 0 | 70·85 | |
| 12 | Roofing with 1st class Mangalore tile roof on teakwood reepers 2″×1″ including fixing, etc., complete | Sqr. | 25 0 0 | 8·83 | |
| 13 | Ridge tiles set in lime mortar and cement pointed | R.ft. | 0 8 0 | 94·50 | |
| 14 | Supplying and fixing T. W. ornamental finials of approved design | Each | 2 0 0 | 3 | |
| 15 | Supplying and fixing T. W. ornamental pendants of approved design | ,, | 1 0 0 | 10 | |
| 16 | Supplying and fixing T. W. ornamental barge board as per approved design | S.ft. | 0 8 0 | 20 | |
| 17 | Chunam plastering | Sqr. | 4 0 0 | 26·14 | |
| 18 | Whitewashing 2 coats as per Item No. 17 | ,, | 0 4 0 | 26·14 | |
| 19 | Government Lac Factory green painting two coats | ,, | 4 0 0 | 3·03 | |
| 20 | Flooring with cement concrete (1 : 2 : 4) 1½″ thick on a bed of 3″ lime jelly concrete (1 : 2) and ½″ cement plastering (1 : 3) finished with red ochre, etc., complete | ,, | 20 0 0 | 3·97 | |
| 21 | Cement pointing to basement (1 : 3) after raking joints | ,, | 3 8 0 | 1·57 | |
| 22 | Supplying and fixing T. W. eaveboard ¾″ thick, 9″ depth | R.ft. | 0 8 0 | 153 | |
| 23 | Supplying and fixing galvanised iron outlet pipes of 1½″ dia. in bath rooms | R.ft. | 1 0 0 | 5 | |
| 24 | Supplying and fixing T. W. racks with suitable frames with iron fittings including 1¼″ thick planks at every 2′ vertical intervals | S.ft. | 1 4 0 | 54 | |
| 25 | Constructing sink and oven in bath room | L. S. | .. | .. | |
| | *III. In-patient Ward.* | | | | |
| 1 | Earthwork excavation for foundation and filling in basement including watering, tamping, etc., complete | C.yd. | 0 4 0 | 27 | |
| 2 | Stone jelly concrete in lime mortar 1 : 2, for foundation | C.ft. | 0 4 0 | 132 | |
| 3 | Size stone in mud including bond stones at 6′ apart with quoin dressing to basement | ,, | 0 4 0 | 589 | |
| 4 | Burnt brick in lime mortar | ,, | 0 4 0 | 767 | |

| No. | Particulars | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 5 | Poviding and fixing burnt stone slabs of 4½" thick roughly dressed and fixed in lime mortar | S.ft. | 0 8 0 | 85 | |
| 5a | Providing and fixing burnt stone slabs of 6" thick in lime mortar for basement with one line dressing to exposed faces and joints | ,, | 0 10 0 | 133 | |
| 6 | Burnt brick in lime composite mortar (1 : 6) pillars with base and capital including white-washing,etc., complete | C.ft. | 0 5 0 | 32 | |
| 7 | Providing and fixing T. W. doors 3"×4" frames with ledged shutters 1¼" thick including iron fittings, etc., complete | S.ft. | 1 8 0 | 58·50 | |
| 8 | Providing and fixing teakwood windows of frames 3"×4" and shutters 1¼" thick with ½" glazed and ½ panelled shutters cut into 4 halves with ¾" iron round bars, iron bolts, nuts, hinges, and screws, etc., complete | ,, | 2 0 0 | 24 | |
| 9 | Providing and fixing T. W. ventilators including iron fittings, etc., complete | ,, | 1 8 0 | 15·5 | |
| 10 | Teakwood wrought and put up including 2 coats of wood oiling, etc., complete | C.ft. | 4 8 0 | 52·89 | |
| 11 | Roofing with 1st class Mangalore tiles on teak-wood reepers 2"×1" including fixing, etc., complete | Sqr. | 25 0 0 | 6·74 | |
| 12 | Ridge tiles set in lime mortar and cement pointed | R.ft. | 0 8 0 | 82 | |
| 13 | Constructing vally line with T. W. planks and zinc sheets, etc., set in cement mortar including plastering, colouring, etc., complete | ,, | 1 0 0 | 28 | |
| 14 | Plastering with chunam mortar | Sqr. | 4 0 0 | 16·15 | |
| 15 | White washing 2 coats as per Item No. 14 | ,, | 0 4 0 | 16·15 | |
| 16 | Providing T. W. pendents as per design | Each | 1 0 0 | 6 | |
| 17 | Providing teakwood finials of approved design | ,, | 2 0 0 | 2 | |
| 18 | Providing and fixing teakwood rack of approved type | S.ft. | 1 4 0 | 60 | |
| 19 | Cement pointing to basement (1 : 3) after raking joints | Sqr. | 3 8 0 | 1·33 | |
| 20 | Painting with Government Lac factory green paint, 2 coats | ,, | 4 0 0 | 2·11 | |
| 21 | Providing teakwood eave board 9" deep ¾" thick including painting as per approved design | R.ft. | 0 8 0 | 99 | |
| 22 | Flooring with 1½" cement concrete (1 : 2 : 4) over 3" lime jelly concrete (1 : 2) including ½" cement plastering (1 : 3) etc., complete with cut line border | Sqr. | 20 0 0 | 3·02 | |
| 23 | Providing sokage pit including lead-off drain, etc., complete | L. S. | .. | .. | |
| 24 | Providing sink including outlet galvanised iron pipes | ,, | .. | .. | |
| | *Alternative items of work that may be found necessary in the execution of work, consistent with the changes that may be made during actual execution.* | | | | |
| 1 | Supplying and fixing burnt stone slabs of 6" thick in lime mortar with two line dressing to exposed faces (for steps) | S.ft. | 0 12 0 | .. | |
| 2 | Supplying and fixing T. W. doors of 3"×4" frames and 1¼" thick shutters, fully panelled with complete iron fittings, etc., complete | ,, | 2 0 0 | .. | |

| No. | Particulars | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 3 | Supplying and fixing T. W. windows, with fully glazed shutters cut into 4 leaves with iron fittings, etc., complete .. .. .. | Sft. | 1 12 0 | .. | |
| 4 | Providing and fixing R.C.C. parapet wall with precast R.C.C. balusters with base and capital as per approved design with plinth and coping slabs of R.C.C. finished as per approved design complete .. .. .. | R.ft. | 2 4 0 | .. | |
| 5 | Providing and fixing R.C.C. fret work ventilators of approved design including one coat of cement wash .. .. .. .. | S.ft. | 1 0 0 | .. | |
| 6 | Constructing R.C.C. pillars with suitable reinforcements 9″ sqr. and 8′ high including centring and curing charges with base and capital as per approved design .. .. | C.ft. | 2 8 0 | .. | |
| 7 | Providing and hoisting Tata's tested R. S. beams including fixing and boxing, etc., complete .. .. .. .. | Cwt. | 18 0 0 | .. | |
| 8 | Providing R.C.C. terrace (1 : 2 : 4) with reinforcements as per design, ceiling, plastered with lime mortar top finished with 3″ of surki concrete well tamped, 2 courses of flat tiles laid on a bed of lime mortar and finished to proper slope with asphaltic mortar including charges for centering, curing, etc., complete— | | | | |
| | (*a*) do 5″ thick .. .. | Sqr. | 85 0 0 | .. | |
| | (*b*) do 4″ thick .. .. | ,, | 75 0 0 | .. | |
| 9 | Supplying and fixing T. W. doors of 3″×4″ frames and 1¼″ thick shutters fully panelled cut into 4 leaves with iron fittings, etc., complete .. .. .. .. | S.ft. | 2 4 0 | .. | |
| 10 | Do with battened shutters cut into four leaves .. .. .. | S.ft. | 1 12 0 | .. | |
| 11 | Cement plastering ½″ thick .. .. .. | Sqr. | 8 0 0 | .. | |

M. A. RAMANUJAM,
*Executive Engineer.*

## CHITALDRUG DIVISION.

*Abstract Notification dated 20th February* 1940.

The attention of the public is invited to the Notification, calling for tenders for "Constructing Linemen's Quarters at Anagod and Vijapur on the Davangere-Chitaldrug Transmission Line, published in Part VI of the *Mysore Gazette*, dated 22nd February 1940 on pages 409-412.

The last date of tender is 9th March 1940 up to 3 P.M.

---

*Notification dated 29th February* 1940.

*ERRATUM.*

GAZETTE NOTIFICATION DATED 20TH FEBRUARY 1940, CALLING FOR TENDERS FOR CONSTRUCTING LINEMEN'S QUARTERS AT ANAGOD AND VIJAPUR ON DAVANGERE-CHITALDRUG TRANSMISSION LINE.

It is hereby notified for the information of the public that the period for completion of the above work noted in para 17 of the above notification should be read as "BY END OF JUNE 1940" instead of "BY END OF DECEMBER 1940".

B. TIRUMALACHAR,
*Executive Engineer.*